

## ITEM WISE BOQ

Tender Inviting Authority: Managing Director, KSFDC.  
Name of Work: Tender for Kalabhvan Theatre Civil Works  
Contract No: 6921/T1/11/KSFDC

Name of the Bidder								
	PRICE SCHEDULE							
Sl. No.	Item Description	A Quantity	Units	B BASIC RATE In Figures To be entered by the Bidder in Rs. P	C TOTAL AMOUNT Without Taxes in Rs. P (A*B)	D GST (18% of Total Amount) in Rs. P (18% of C)	TOTAL AMOUNT With Taxes in Rs. P (C+D)	TOTAL AMOUNT In Words
1.01	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 meters lead:With cement mortar 1:4 ( 1 cement : fine sand)	52.5	Sq m					
1.02	6 mm cement plaster of mix:1:3 ( 1 cement : 3 fine sand)	7.8	Sq m					
1.03	9 mm cement plastering of mix : 1:3 (1 cement : 3 fine sand ) including all cost of materials, labour charges etc complete	7.2	Sq m					
1.04	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+0.05%), total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x55mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	13	Sq m					
1.05	Steel work in built up G I tubular ( round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting,fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete	50	Kg					
1.06	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface:Water thinnable cement primer	52.5	sq m					
1.07	Finishing walls with Acrylic Smooth exterior paint of required shade:New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	52.5	sq m					
2.00	Lumsum Heading LS amount for Site Clearence and petty works	1	LS					
Total in Figures								
Quoted Rate in Figures								
Quoted Rate in Words								